

PLANNING AND DESIGNING STANDARD OF RURAL ROAD CONSTRUCTION - AN EXPLORATORY STUDY: A CASE OF LUSAKA PROVINCE IN ZAMBIA

Erastus M. MWANAUMO¹ and Ephraim SAKALA²

^{1&2} Department of Civil and Environmental Engineering, School of Engineering,
University of Zambia, P.O. Box 32379, Lusaka, Zambia

Email: Erastus.mwanaumo@unza.zm¹; ephraimsakala@yahoo.com²

ABSTRACT

The state of rural roads in Zambia is very poor and in a deplorable condition. Drainages are missing, or where they exist, they are narrow, inadequate and not constructed correctly. Bridges are missing, old, inadequate or wrongly constructed and usually very poorly maintained. In most roads, the shoulders are not stable. From reviewed literature, several gaps in the planning, design, specifications, funding and general roads management in Zambia were identified as being the root causes of poor-quality rural roads. An in-depth literature review was carried out as secondary sources using journals, rural road construction handbook, peer reviewed articles, dissertations and the internet. In-depth interviews were further carried out with the staff at Ministry of Finance, Road Development Agency (RDA), National Road Fund Agency (NRFA), National Council for Construction (NCC), Rural Road Unit and also the Royal Highnesses and their subjects in Chongwe and Lusaka North areas. The results show that the planning is adequate but the problem lies with the planning personnel who are not adequately trained to undertake the tasks. Designs and specifications needed to consider the alignment requirements, technical performance, pavement solutions, material requirements and structures that are specific to an area. Results indicate that planners use a one-size fits all approach kind of designing resulting in the quality deficiency in some areas. The research assist government in developing and disseminating improved policies that assists in better planning, constructing and maintenance of rural roads. It introduces mitigatory actions and recommendations which the government can utilize in coming up with sustainable and reliable quality rural roads.

Keywords: Rural, Roads, quality, compaction, Transmitter road design.

1. INTRODUCTION

It has been acknowledged that rural roads should be treated as the last link of the transport network. Despite this, they often form the most important link in terms of providing access for the rural population. Their permanent or seasonal absence acts as a crucial factor in terms of the access of rural communities to basic services such as education, primary health care, water supply, local markets and economic opportunities (Donnges, 2003). In a study in Ethiopia (Dercon et al., 2008) on 15 villages that were surveyed between 1994 and 2004, they concluded that access to all – weather rural roads reduced poverty by 6.9 per cent and increased consumption growth by 16.3 per cent. Dercon and Hoddinott (2005) found that, in Ethiopia, an increase of 10 km in the distance from the rural village to the closest market town had a dramatic effect on the likelihood that the household purchased inputs. Mu and Van de Walle (2007) showed that markets in Vietnam were more likely to develop as a result of rural road improvements where communities had access to extended networks of transport infrastructure.

It was shown in Uganda that benefits from improving access to basic education depended on complementary investments in infrastructure (Deininger and Okidi, 2003). Road improvements in Bangladesh led to lower input and lower transportation costs, higher production, higher wages and higher output prices (Khandker et al., 2011). Access to rural roads in Nepal improved the productive capacity of poor households (Jacoby, 2000). Rural road rehabilitation in Georgia increased the opportunities for off – farm and female wage employment (Lokshin and Yemtsov, 2005). Rehabilitation and maintenance of rural roads in Peru improved access and attendance to schools and child health centres (Escobal and Ponce, 2003). According to The Rural Accessibility Index of 2010 and also Torero and Chowdhury, 2004, majority of rural communities in Africa have inadequate and unreliable infrastructure services with only 34% of rural Africans living within 2 kilometres of an all – weather road compared to 59% in Latin America, 65% in East Asia and over 90% in other developed regions. Africa Infrastructure Country Diagnostic of 2010 indicated that even where feeder roads exist; the rural environment presents particular institutional challenges for road maintenance. Only half of the existing rural road network is in good or fair condition, which is much lower than the 80% found for the inter – urban network.

Pinstrup – Anderson and Shimokawa (2010) and Fan (2011) indicated that the provision of rural infrastructure contributed to the delivery of goods and services that promoted prosperity and growth, contributed to quality of life, including social well – being, health and safety, and the quality of the environment. It will help reduce the cost of inputs and transport to markets, also increase farmer’s access to enlarged markets, facilitate trade flow and spur value addition and crowd – in investment. Foster and Briceno – Garmendia in 2010 stated that the variation in road quality throughout the various Sub Saharan African countries reflected several interacting factors. Firstly, the relation to affordability where the GDP per capita is most strongly correlated with the percentage of the main road network in good condition, signifying that richer countries tended to spend more on maintenance. No such clear relationship exists for rural roads. The second factor relates to topographic and climatic influences where mountainous and wet countries normally have poorer road conditions in both main and rural networks (Johannessen, 2008). Thirdly, they observed that countries with road funds and road agencies have considerably better road conditions than those that have neither.

Addo – Abedi, in 2007 noted that a number of African countries had embarked on reforms in the last few decades supported by four “building blocks” namely Ownership, Financing, Responsibility and Management. The main aim of the reforms was to manage roads as a business and bring them into the market place by charging for road use on a fee – for – service basis. The mean distance to services and community assets diminished significantly due to rehabilitation of rural roads in Zambia’s eastern province (Kingombe, 2011). The purpose of this study therefore is:

1. To review whether the planning of rural road construction in Lusaka province is adequate.
2. To determine whether the design standards and the technology used in Lusaka province are appropriate.

2. RESEARCH METHODOLOGY

Primary data was collected through three check lists that were filled with data collected through observations and field measurements. To help the researcher understand how to collect this data, the researcher had to undergo Rural Road Construction and Maintenance training with The National Council for Construction for a period of four months. This programme consisted of two parts: The theory part comprising Mathematics, Road Rehabilitation and Maintenance, Construction Materials, Construction Management,

Pricing and Bidding, Communication Skills and Entrepreneurship and the Practical part comprising Road Rehabilitation and Maintenance only.

The research also relied on supplementary secondary data that was readily available from;

- National Road Fund Agency
- Road Development Agency
- National Council for Construction
- Ministry of Transport, Communication, Works and Supply
- Ministry of Local Government and Housing
- Ministry of Finance

Three areas were picked because of proximity, less transport cost, security reasons, assuredly supervised roads, ease of contacting the contractors and also the ease of sourcing the contract documents from the ministries involved. Two rural roads per area were also picked at random. Road dimension tests, road profile tests and physical check of the road features were conducted on the full length of these rural roads. The first test was the road dimension test using tapes to check the accuracy of the carriageway and the side drains. The second test was the road profile test using the line level where the camber of the carriageway and the longitudinal profile of the carriageway were checked and the final test was the visual test that was checking for the presence of culverts, culvert rings, wing walls, headwalls, ramps, outfalls, mitre drains, scour checks, laybys, ditch and the shoulder and these were presented in the form of check lists. The following were the check lists used:

2.1 Road Dimension Tests

The standard cross section of rural roads in Zambia is one having a carriageway of 5.5m, with a gravel coarse of 5m span, side slope of 1.2m, a ditch of 1m and a back slope of minimum 3:1 and a maximum of 1:1. Type of Tests carried out were simple checks on the dimensional accuracy of the construction works using measuring Tapes.

To Test for the camber of the carriageway and Checking on the longitudinal profile of the carriageway, the research used the line level. For the simple checks on the dimensional accuracy of the construction works, measuring Tapes were used.

2.2 Road Profile Tests

Two types of Tests were carried out.

1. Check on the camber of the carriageway
2. Check on the longitudinal profile of the carriageway

For both of them the line level was used.

2.3 Gravel Layer Test

To test the gravel for thickness of compaction and Degree of compaction, measuring Tapes and special laboratory tests were carried out.

2.3.1 Compaction

The compaction method is usually specified. The following are factors that can influence compaction.

- Moisture content
- Amount of compaction
- Thickness of layer

2.4 The Study Population and Sample

Leedy and Ormrod (2010) mention a two-stage descriptive survey as one of the means of data collection. In this study, the second stage data collection of descriptive survey was used. This approach works through collection of quantitative data coming from a designed checklist. This specific checklist was used for recording measurements from field survey. The target area being the sampled population was divided into three:

- a. Two rural roads in Chongwe
- b. Two rural roads in Lusaka West
- c. Two rural roads in Lusaka North

2.5 Interviews and Checklist

Under qualitative analysis, structured interviews with headmen and their subjects, staff at National Council for Construction, Ministry of Finance staff, National Road Fund Agency staff, Ministry of Works and Supply and Ministry of Local Government and Housing staff were conducted. The data collected was used to come up with an informed opinion that was correlated to measurements collected. The results helped to identify the gaps in specifications and implementation. A desktop study using published literature on rural roads was also carried out.

Interviews and in-depth discussions were carried out with engineers under the Rural Road Unit and The National Council for Construction. This was done in order to understand the challenges that they went through and the successes as well. The interviews were aimed at obtaining preliminary data that would enhance the measurements. The interviews were limited to participants within Lusaka, the capital city, due to the short time that was required to get preliminary data and also due to the cost implications. Security reasons were also taken into account as the field visits required walking the whole length of the sampled rural road. A check list was adopted as the main research instrument which was based on the advantages that a representative sample would be realised with little time or costs. It was explained to the participants who assisted in the measurements. It was accompanied with a cover letter. The tool that was used in the research was a semi structured checklist. Interviews were another means of data collection and field measurements.

2.6 The Study Area

The study area was Lusaka Province. Lusaka province is one of the 10 provinces in Zambia. It is located in the southern part of the country. Lusaka province was taken because of its proximity to the ministries hence reducing on transport costs and lodging fees. Also, it was much easier to access data from the concerned institutions. Even interviews were easier to conduct with the officials as well. Efforts to prevent variability in sample size and analysis were made. The sample size was confined to Lusaka province because according to statistics, most of the rural roads are concentrated around the province.

3. FINDINGS AND DISCUSSION

The following data was collected on six rural roads from Lusaka West, Chongwe and Lusaka North areas. The results were compared to theory with the view of finding out whether our rural roads are built to specifications, or if not, why?




Figure 1. Network Condition – Paved TMD (Source: Road Sector Annual Work Plan for 2014)

In Zambia, the Road Development Agency undertakes annual surveys to determine the road condition indices for unpaved roads within the Core Road Network. The variations are considerable, as can be seen in figures 4-1 and 4-2 which give the status of the condition on the Core Road Network. For example, during the period 2014/2015 over 70% of unpaved Trunk, Main and District roads and 82% of the unpaved Primary Feeder Roads were in poor condition. The condition of PFR substantially remained unchanged.




Figure 2. Network Condition – Unpaved TMD (Source: Road Sector Annual Work Plan for 2014)

It is clear from the findings that the planning process is followed adequately. It starts from the National Development Plans to The Transport Sector Plans. These are then incorporated into the Annual programs and Budgets. Local plans are then drawn from them. That is when Project plans are done and then the Detailed plans and finally the Maintenance plans are done. All these plans are governed by a Legal and Regulatory framework.

The Roads in Zambia are properly classified and those providing access to and from local communities are often under the jurisdiction of the local authorities. The government develops a set of design guidelines. These design guidelines include general directions on the geometric features of the roads, such as appropriate dimensions of the road cross – section and curvature, surfacing options, drainage solutions and road reserves. All public expenditure is governed by a comprehensive set of procedures and directives detailing how funds are to

be used and accounted for. These procedures include budgeting and accounting procedures as well as detailed regulations on the contracting arrangements.

The planning process forms the basis for all budgeting and resource scheduling required in civil works projects. Roads to be constructed, improved or maintained under a particular programme are not selected in an arbitrary manner. These are done in distinct stages. The initial identification is the first step in the preparation of a list of proposed roads to be improved and maintained. This initial list is in most cases prepared with the involvement of the local communities and it must meet the pre – determined criteria by the central government. This is done in order to qualify or disqualify those roads that meet or don't meet certain criteria, are or aren't technically or economically feasible or are likely or not likely to have the expected impact. Local participation in the ranking of projects for screening is through elected representatives.

A more detailed assessment for supporting investment Cost needs is estimated and socioeconomic data assembled. After the screening and the appraisal stage, roads are selected against the limited resources. The roads are then ranked based on social impact, economic impact, and environmental impact. The road with the best score is then selected. As in all infrastructure works, the three main criteria for finally selecting a rural road are Technical Feasibility, Economic Justification and Social Considerations.

On the spot check on six rural roads that were picked in Lusaka North, Lusaka West and Chongwe, the following data was collected.

Transmitter Road in Lusaka West of Lusaka District

Total Length of Road: 2.5km; Carriageway: 5.5m.

Table 1. Transmitter Road Dimension Test (Rural road dimension test using the tape)

| Test | Average | Location | Every | Tolerance |
|--------------------------------|----------------|----------|-------|-----------|
| Width of carriageway | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.5m, and 0.2m | Field | 10m | +/- 20mm |

Table 2. Transmitter Road Profile Test (Rural road dimension test using the line level)

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | 0.1m | Field | 20m | +/- 10mm |
| Longitudinal profile | - | Field | 20m | +/- 50mm |

Table 3. Transmitter Road Condition Inventory Check List

| Road Condition Inventory | Specifications | Comments |
|--------------------------|--------------------------------------|----------------------------------|
| Soil Type | Laterite | Laterite soil present |
| Surface Material | Laterite | Laterite |
| Road Surface Width | 5.5m | 5.5m |
| Maximum Gradient | 12% | <6% |
| Camber | 5% after compaction | 5% |
| Shoulder | 1.2m | 1m |
| Side Slope | 1:4 | 0.2m |
| Side Drain Left | 1m | 0.5m |
| Side Drain Right | 1m | 0.5m |
| Tree and Stump Removal | 6m clearance from centre | Not adhered to |
| Sand Removal | Must be removed | Done |
| Boulder Removal | <0.5m boulders buried along the road | No presence of boulders observed |
| Clear Side Drain | Must be cleared | Overgrown with grass |
| Clear Mitre Drains | Must be cleared | Overgrown with grass |
| Scour Checks | 12% gradient must be 6m apart | No Scour Checks observed |

| | | |
|--------------------------|---------------------------------------------|-----------------------------------------------|
| Grass Planting | Must be done | Done |
| Catch Water Drains | 5m away from the Ditch | Present but less than 5m from the Side Drain |
| Gravel Surface Thickness | 125mm after compaction | Less than 50mm thickness |
| Culverts per km | For Maximum Gradients of 12%, 2 to 4 per km | No Culvert for the entire stretch of the road |
| Culvert Pipe Size | 600mm | No Culverts Pipes present |
| Wing Walls | 45°<Centreline<75° | No Wing Walls present |
| Head Walls | 200mm | No Head Walls present |
| Ramp | 20m approach distance | No Ramp present |
| Layby | 5m | No Layby found |

China – Zambia Road in Lusaka West of Lusaka District

Total Length: 1.9 km; Carriageway: 5.5m

Table 4. China – Zambia Road Dimension Test

| Test | Average | Location | Every | Tolerance |
|--------------------------------|---------------|----------|-------|-----------|
| Width of carriage | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.8m and 0.2m | Field | 10m | +/- 20mm |

Table 5. China – Zambia Road Profile Test

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | <0.1m | Field | 20m | +/- 10mm |
| Longitudinal profile | - | Field | 20m | +/- 50mm |

Table 6. China – Zambia Road Condition Inventory Check List

| Road Condition Inventory | Specifications | Comments |
|--------------------------|---------------------------------------------|-----------------------------------------------|
| Soil Type | Laterite | Laterite soil present |
| Surface Material | Laterite | Laterite |
| Road Surface Width | 5.5m | 5.5m |
| Maximum Gradient | 12% | <6% |
| Camber | 5% after compaction | 5% |
| Shoulder | 1.2m | 1m |
| Side Slope | 1:4 | 0.2m |
| Side Drain Left | 1m | 0.8m |
| Side Drain Right | 1m | 0.8m |
| Tree and Stump Removal | 6m clearance from centre | Not adhered to |
| Sand Removal | Must be removed | Done |
| Boulder Removal | <0.5m boulders buried along the road | Presence of boulders observed along the road |
| Clear Side Drain | Must be cleared | Overgrown with grass |
| Clear Mitre Drains | Must be cleared | Overgrown with grass |
| Scour Checks | 12% gradient must be 6m apart | No Scour Checks observed |
| Grass Planting | Must be done | Done |
| Catch Water Drains | 5m away from the Ditch | Present but less than 5m from the Side Drain |
| Gravel Surface Thickness | 125mm after compaction | 125mm thickness |
| Culverts per km | For Maximum Gradients of 12%, 2 to 4 per km | No Culvert for the entire stretch of the road |
| Culvert Pipe Size | 600mm | No Culverts Pipes present |
| Wing Walls | 45°<Centreline<75° | No Wing Walls present |

| | | |
|------------|-----------------------|-----------------------|
| Head Walls | 200mm | No Head Walls present |
| Ramp | 20m approach distance | No Ramp present |
| Layby | 5m | No Layby found |

Kapepe School to Nyendwa Bar Road in Chongwe District

Total Length: 10.8 km; Carriageway: 5.5m

Table 7. Kapepe – Nyendwa Road Dimension Test

| Test | Average | Location | Every | Tolerance |
|--------------------------------|--------------|----------|-------|-----------|
| Width of carriage | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.5m and 0.2 | Field | 10m | +/- 20mm |

Table 8. Kapepe – Nyendwa Road Profile Test

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | <0.1m | Field | 20m | +/- 10mm |
| Longitudinal profile | - | Field | 20m | +/- 50mm |

Table 9. Kapepe – Nyendwa Road Condition Inventory Check List

| Road Inventory | Condition | Specifications | Comments |
|--------------------------|-----------|---------------------------------------------|-----------------------------------|
| Soil Type | | Laterite | Laterite soil present |
| Surface Material | | Laterite | Laterite |
| Road Surface Width | | 5.5m | 5.5m |
| Maximum Gradient | | 12% | <6% |
| Camber | | 5% after compaction | 5% |
| Shoulder | | 1.2m | 1m |
| Side Slope | | 1:4 | 0.2m |
| Side Drain Left | | 1m | 0.5m |
| Side Drain Right | | 1m | 0.5m |
| Tree and Stump Removal | | 6m clearance from centre | Adhered to specifications |
| Sand Removal | | Must be removed | Done |
| Boulder Removal | | <0.5m boulders buried along the road | No presence of boulders observed |
| Clear Side Drain | | Must be cleared | Overgrown with grass |
| Clear Mitre Drains | | Must be cleared | Overgrown with grass |
| Scour Checks | | 12% gradient must be 6m apart | No Scour Checks observed |
| Grass Planting | | Must be done | Done |
| Catch Water Drains | | 5m away from the Ditch | Present at 5m from the Side Drain |
| Gravel Surface Thickness | | 125mm after compaction | Less than 50mm thickness |
| Culverts per km | | For Maximum Gradients of 12%, 2 to 4 per km | Two Culverts per km observed |
| Culvert Pipe Size | | 600mm | 300mm Culverts Pipes |
| Wing Walls | | 45°<Centreline<75° | Not to specifications |
| Head Walls | | 200mm | Not to specifications |
| Ramp | | 20m approach distance | < 20m approach distance |
| Layby | | 5m | No Layby found |

Evergreen to Nyendwa Road in Chongwe District

Total Length: 9km; Carriageway: 5.5m

Table 10. Evergreen – Nyendwa Road Dimension Test

| Test | Average | Location | Every | Tolerance |
|--------------------------------|---------------|----------|-------|-----------|
| Width of carriage | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.6m and 0.1m | Field | 10m | +/- 20mm |

Table 11. Evergreen – Nyendwa Road Dimension Test

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | 0.2m | Field | 20m | +/- 10mm |
| Longitudinal profile | | Field | 20m | +/- 50mm |

Table 12. Evergreen – Nyendwa Road Condition Inventory Check List

| Road Inventory | Condition | Specifications | Comments |
|--------------------------|-----------|---------------------------------------------|----------------------------------|
| Soil Type | | Laterite | Laterite soil present |
| Surface Material | | Laterite | Laterite |
| Road Surface Width | | 5.5m | 5.5m |
| Maximum Gradient | | 12% | <6% |
| Camber | | 5% after compaction | 5% |
| Shoulder | | 1.2m | 1m |
| Side Slope | | 1:4 | 0.1m |
| Side Drain Left | | 1m | 0.6m |
| Side Drain Right | | 1m | 0.6m |
| Tree and Stump Removal | | 6m clearance from centre | Adhered to |
| Sand Removal | | Must be removed | Done |
| Boulder Removal | | <0.5m boulders buried along the road | No presence of boulders observed |
| Clear Side Drain | | Must be cleared | Cleared |
| Clear Mitre Drains | | Must be cleared | Cleared |
| Scour Checks | | 12% gradient must be 6m apart | Scour Checks observed |
| Grass Planting | | Must be done | Done |
| Catch Water Drains | | 5m away from the Ditch | Present and at 5m |
| Gravel Surface Thickness | | 125mm after compaction | Spot gravelling 125mm thickness |
| Culverts per km | | For Maximum Gradients of 12%, 2 to 4 per km | 6 Culverts |
| Culvert Pipe Size | | 600mm | 300mm Culverts Pipes |
| Wing Walls | | 45°<Centreline<75° | Present |
| Head Walls | | 200mm | Present |
| Ramp | | 20m approach distance | Ramp present |
| Layby | | 5m | No Layby found |

Headman Mpandika's Palace Road in Lusaka North

Total Length: 4.2km; Carriageway: 5.5m

Table 13. Mpandika Palace Road Dimension Test

| Test | Average | Location | Every | Tolerance |
|--------------------------------|-------------|----------|-------|-----------|
| Width of carriage | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.6m & 0.2m | Field | 10m | +/- 20mm |

Table 14. Mpandika Palace Road Profile Test

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | 0.1m | Field | 20m | +/- 10mm |
| Longitudinal profile | | Field | 20m | +/- 50mm |

Table 15. Mpandika Palace Road Condition Inventory Check List

| Road Inventory | Condition | Specifications | Comments |
|--------------------------|-----------|---------------------------------------------|----------------------------------|
| Soil Type | | Laterite | Laterite soil present |
| Surface Material | | Laterite | Laterite |
| Road Surface Width | | 5.5m | 5.5m |
| Maximum Gradient | | 12% | 12% |
| Camber | | 5% after compaction | 5% |
| Shoulder | | 1.2m | 1m |
| Side Slope | | 1:4 | 0.2m |
| Side Drain Left | | 1m | 0.6m |
| Side Drain Right | | 1m | 0.6m |
| Tree and Stump Removal | | 6m clearance from centre | Adhered to |
| Sand Removal | | Must be removed | Done |
| Boulder Removal | | <0.5m boulders buried along the road | No presence of boulders observed |
| Clear Side Drain | | Must be cleared | Overgrown with grass |
| Clear Mitre Drains | | Must be cleared | Overgrown with grass |
| Scour Checks | | 12% gradient must be 6m apart | No Scour Checks observed |
| Grass Planting | | Must be done | Done |
| Catch Water Drains | | 5m away from the Ditch | Not Present |
| Gravel Surface Thickness | | 125mm after compaction | Earth road |
| Culverts per km | | For Maximum Gradients of 12%, 2 to 4 per km | 3 Culverts |
| Culvert Pipe Size | | 600mm | 600mm Culverts Pipes |
| Wing Walls | | 45°<Centreline<75° | No Wing Walls present |
| Head Walls | | 200mm | Head Walls present |
| Ramp | | 20m approach distance | No Ramp present |
| Layby | | 5m | No Layby found |

Spin-Along Road in Lusaka North

Total Length: 3.2km; Carriageway: 5.5m

Table 16. Spin - Along Road Dimension Test

| Test | Average | Location | Every | Tolerance |
|--------------------------------|---------------|----------|-------|-----------|
| Width of carriage | 5.5m | Field | 300m | +/- 50mm |
| Width and depth of side drains | 0.5m and 0.3m | Field | 10m | +/- 20mm |

Table 17. Spin - Along Road Profile Test

| Test | Average | Location | Test Interval | Tolerance |
|----------------------|---------|----------|---------------|-----------|
| Camber | 0.1m | Field | 20m | +/- 10mm |
| Longitudinal Profile | Ok | Field | 20m | +/- 50mm |

Table 18. Spin - Along Road Condition Inventory Check List

| Road Inventory | Condition | Specifications | Comments |
|----------------|-----------|----------------|-----------------------|
| Soil Type | | Laterite | Laterite soil present |

| | | |
|--------------------------|---------------------------------------------|-----------------------------------------------|
| Surface Material | Laterite | In situ Laterite |
| Road Surface Width | 5.5m | 5.5m |
| Maximum Gradient | 12% | <6% |
| Camber | 5% after compaction | 5% |
| Shoulder | 1.2m | No Shoulder observed |
| Side Slope | 1:4 | 0.3m |
| Side Drain Left | 1m | 0.5m |
| Side Drain Right | 1m | 0.5m |
| Tree and Stump Removal | 6m clearance from centre | Adhered to |
| Sand Removal | Must be removed | Done |
| Boulder Removal | <0.5m boulders buried along the road | No presence of boulders observed |
| Clear Side Drain | Must be cleared | Overgrown with grass |
| Clear Mitre Drains | Must be cleared | Overgrown with grass |
| Scour Checks | 12% gradient must be 6m apart | No Scour Checks observed |
| Grass Planting | Must be done | Done |
| Catch Water Drains | 5m away from the Ditch | Not Present |
| Gravel Surface Thickness | 125mm after compaction | No gravel |
| Culverts per km | For Maximum Gradients of 12%, 2 to 4 per km | No Culvert for the entire stretch of the road |
| Culvert Pipe Size | 600mm | No Culverts Pipes present |
| Wing Walls | $45^\circ < \text{Centreline} < 75^\circ$ | No Wing Walls present |
| Head Walls | 200mm | No Head Walls present |
| Ramp | 20m approach distance | No Ramp present |
| Layby | 5m | No Layby found |

4. LIMITATIONS

This research was only conducted in Lusaka West, Chongwe and Lusaka North areas because most of the ministries and agencies responsible for rural road design, approval, procurement, construction and supervision are located in Lusaka. Coupled to this were also issues of limited resources and time constraints. Security concerns to the researcher were also considered. Only two rural roads per area were selected arbitrarily and assessed to help understand the level of the problem.

Another limiting factor was the scarce availability of data on causes of poor quality of rural roads. That which exists is often not readily available or tailored to local conditions. Engineering guidelines are either very old or have not been refined in recent years to exploit possible potential cost savings. There are inadequacies in knowledge also and the issues of climate change adaptation and mitigation pose difficult questions about how to design, plan and build resilient rural roads and transport services without incurring even greater costs, either on the environment or on strained government budgets.

5. RECOMMENDATION

The potential contribution of rural roads to the socio – economic development of Zambia cannot be overemphasised. The impact of quality rural road infrastructure could be far – reaching, going beyond poverty reduction – a goal which many leaders now view as unambitious – to sustain economic growth and structural transformation. Zambia’s large and sparsely populated landmass underscores the relevance and important role of rural roads in the successful implementation of most, if not all, development policies. In essence, poor quality rural road systems negatively affect other sectors of the economy.

1. The Public Service Management Division must recruit qualified personnel to fill up the vacant positions. The local councils must be encouraged to employ competent people who will help, especially during the planning process, to come with detailed plans, project plans and local plans. These when forwarded to Central government will help with the formulation of Annual Programmes and Budgets, Transport Sector Plans and finally National Plans. This will assist in limiting Central Government's role to coordination, guidance and oversight, policy, formulating guidelines and providing technical support in planning and contract management thereby reducing bureaucracy particularly in making payments to contractors.
2. Design standards should be based on reliability and durability not just concentrating on accessibility. We need rural roads that are adequate, cost effective and sustainable. Standards such as economic road access should place importance on essential access, spot surface improvement in critical seasons, on surface drainage and essential structures rather than on geometric characteristics determined by design speed. Attention must also be paid to topography.

6. REFERENCES

- Addo-Abedi, F.Y. (2007). Sustainable Rural Road Financing and Investment. Arusha, Tanzania
- Deininger, K., and Okidi, J. (2003). Growth and Poverty reduction in Uganda, 1992-2000: Panel Data Evidence. Development Policy Review No. 2(4): 481-509
- Dercon, S., and Hoddinott, J. (2005). Impact of Agricultural Extension and Roads on Poverty and Consumption. Agricultural and Applied Economics Association, Oxford, England.
- Donnges, C. (2003). Improving Access in Rural Areas; Guidelines for Integrated Rural Accessibility Planning. Assist-AP Rural Infrastructure Publication, No.1. International Labour Organisation, Bangkok.
- Escobal, J., and Ponce, C. (2003). The Benefits of Rural Roads: Enhancing Income Opportunities for the Rural Poor. Grade Working Paper 40
- Fan, H. (2011). Rural Road Maintenance in China: Planning for Accessibility and Rural Roads. Transport and Communications Bulletin for Asia and the Pacific, No. 81, ESCAP, United Nations, Bangkok, pp. 52-68
- Foster, V., and Briceno – Garmendia, (Eds.). (2010). Africa's Infrastructure: A Time for Transformation. The International Bank for Reconstruction and Development and The World Bank, Washington DC.
- Johannessen, B. (2008). Building rural roads – Bangladesh: International Labour Organisation
- Khandker, S. R., and Koolwal, B. G. (2011). Estimating the long-Term Impacts of Rural Roads: A Dynamic Panel Approach. WPS 5867. World Bank, Washington, DC
- Kingombe, C. (2011). Achieving pro-poor growth through investment in rural feeder roads: the role of impact evaluation. ODI.
- Lokshin, M., and Yemtsov, R. (2005). The Poverty Impacts of Rural Roads: Evidence from Bangladesh. ILO
- Mu, R. and Van de Walle, D. (2007). Rural Roads and Poor Area Development in Vietnam. World Bank Policy Research Working Paper 4340
- Pinstrup- Anderson, P., and Shimokawa, S. (2010). Rural Infrastructure and Agriculture Development. Paper presented at the Annual Bank Conference on Development Economics. Tokyo, Japan.
- Rural Roads Unit. (2011). Performance report, 2008 – 2011. Government Printers, Lusaka, Zambia.
- Torero, M., and Chowdhury, S. (2004). Increasing Access to Infrastructure for Africa's Rural Poor. International Food Policy Research Institute, European Commission.